



BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

Name of Work: Maintenance of Crematorium, Burrial Grounds & Office
Maintenance in Ward No 14 Bagalagunte, Dasarahalli Sub Division

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures	In Words (Rs)
1	2	3	4	5	6
1	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	Cum Sqm	16650.00	~~6.36~~ 6.00	Rupees Six & thirty six Paise Only
2	Excavation for roadway in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal and trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications..	Cum	337.50	~~350.00~~ 386.90	Three hundred Rupees Three Hundred eighty six & Ninty Paise Only J. S. S.


Signature of the Contractor


Executive Engineer
Dasarahalli Division